

**GEOTECHNICAL ENGINEERING INVESTIGATION
PROPOSED APARTMENT AND RETAIL BUILDING
2218 W. YOSEMITE AVENUE
MANTECA, CALIFORNIA**

PROJECT NO. 072-25004
APRIL 15, 2025

Prepared for:

**MR. KEVIN LANG
MCR ENGINEERING
1242 DUPONT COURT
MANTECA, CALIFORNIA 95336**

Prepared by:

**KRAZAN & ASSOCIATES, INC.
GEOTECHNICAL ENGINEERING DIVISION
448 MITCHELL ROAD SUITE C
MODESTO, CALIFORNIA 95354
(209) 572-2200**



GEOTECHNICAL ENGINEERING • ENVIRONMENTAL ENGINEERING
CONSTRUCTION TESTING & INSPECTION

April 15, 2025

Project No. 072-25004

Mr. Kevin Lang
MCR Engineering
1242 Dupont Court
Manteca, California 95336

**RE: Geotechnical Engineering Investigation
Proposed Apartment and Retail Building
2218 W. Yosemite Avenue
Manteca, California**

Dear Mr. Lang:

In accordance with your request, we have completed a Geotechnical Engineering Investigation for the above-referenced site. The results of our investigation are presented in the attached report.

If you have any questions or if we may be of further assistance, please do not hesitate to contact our office at (209) 572-2200.



Respectfully submitted,
KRAZAN & ASSOCIATES, INC.

David R. Jarosz, II
Managing Engineer
RGE No. 2698/RCE No. 60185

DRJ:ht

Offices Serving the Western United States

448 Mitchell Road, Suite C • Modesto CA 95354 • (209) 572-2200 • Fax: (209) 572-2206

07225004 Report (Apartment and Retail Building)

TABLE OF CONTENTS

INTRODUCTION	1
PURPOSE AND SCOPE.....	1
PROPOSED CONSTRUCTION	2
SITE LOCATION AND SITE DESCRIPTION	2
GEOLOGIC SETTING	2
FIELD AND LABORATORY INVESTIGATIONS	3
SOIL PROFILE AND SUBSURFACE CONDITIONS	4
PERCOLATION TESTING.....	4
GROUNDWATER.....	5
SOIL LIQUEFACTION.....	5
CONCLUSIONS AND RECOMMENDATIONS.....	6
Administrative Summary	6
Groundwater Influence on Structures/Construction.....	7
Site Preparation - General	8
Supplemental Site Preparation - Liquefaction Minitigation - Geogrid	10
Engineered Fill.....	10
Drainage and Landscaping	11
Utility Trench Backfill	11
Foundations - Conventional	12
Floor Slabs and Exterior Flatwork	13
Lateral Earth Pressures and Retaining Walls	13
R-Value Test Results and Pavement Design.....	14
Seismic Parameters – 2022 CBC.....	16
Soil Cement Reactivity.....	16
Compacted Material Acceptance.....	16
Testing and Inspection	17
LIMITATIONS.....	17
SITE PLAN	19
LOGS OF BORINGS (B1 TO B8).....	Appendix A
GENERAL EARTHWORK SPECIFICATIONS.....	Appendix B
GENERAL PAVING SPECIFICATIONS	Appendix C

April 15, 2025

Project No. 072-25004

**GEOTECHNICAL ENGINEERING INVESTIGATION
PROPOSED APARTMENT AND RETAIL BUILDING
2218 W. YOSEMITE AVENUE
MANTECA, CALIFORNIA**

INTRODUCTION

This report presents the results of our Geotechnical Engineering Investigation for the proposed apartment and retail building to be located at 2218 W. Yosemite Avenue in Manteca, California. Discussions regarding site conditions are presented herein, together with conclusions and recommendations pertaining to site preparation, Engineered Fill, utility trench backfill, drainage and landscaping, foundations, concrete floor slabs and exterior flatwork, retaining walls, soil cement reactivity, and pavement design.

A site plan showing the approximate boring locations are presented following the text of this report. A description of the field investigation, boring logs, and the boring log legend are presented in Appendix A. Appendix A also contains a description of the laboratory-testing phase of this study, along with the laboratory test results. Appendices B and C contain guides to earthwork and pavement specifications. When conflicts in the text of the report occur with the general specifications in the appendices, the recommendations in the text of the report have precedence.

PURPOSE AND SCOPE

This investigation was conducted to evaluate the soil and groundwater conditions at the site, to make geotechnical engineering recommendations for use in design of specific construction elements, and to provide criteria for site preparation and Engineered Fill construction.

Our scope of services was outlined in our proposal dated December 16, 2024 (KA Proposal No. P904-24) and included the following:

- A site reconnaissance by a member of our engineering staff to evaluate the surface conditions at the project site.
- A field investigation consisting of drilling 8 borings to depths ranging from approximately 10 to 50 feet for evaluation of the subsurface conditions at the project site.
- Performing laboratory tests on representative soil samples obtained from the borings to evaluate the physical and index properties of the subsurface soils.

- Evaluation of the data obtained from the investigation and an engineering analysis to provide recommendations for use in the project design and preparation of construction specifications.
- Preparation of this report summarizing the results, conclusions, recommendations, and findings of our investigation.

PROPOSED CONSTRUCTION

We understand that design of the proposed development is currently underway; structural load information and other final details pertaining to the structures are unavailable. On a preliminary basis, it is understood that development will cover approximately 4.56 acres and include the construction of a new apartment and retail building. It is anticipated the apartment building will be a five-story structure with an associated clubhouse. The retail building will be a 2-story structure. The buildings are planned to be wood-framed structures utilizing concrete slab-on-grade construction. Foundation loads are anticipated to be light to moderate. On-site paved areas, drainage swales, and landscaping are also planned for the development of the project.

In the event these structural or grading details are inconsistent with the final design criteria, the Soils Engineer should be notified so that we may update this writing as applicable.

SITE LOCATION AND SITE DESCRIPTION

The site is rectangular in shape and encompasses approximately 4.56 acres. The site is located approximately 665 feet west of Airport Way, on the south side of W. Yosemite Avenue in Manteca, California. The site has a street address of 2218 W. Yosemite Avenue. The site is surrounded by rural residential developments with large yards to the east and west; W. Yosemite Avenue and a vacant field to the north; and a vacant field to the south.

The site is currently developed with approximately five residences or living units in the northeast portion, a single-family residence in the northwest portion, wood and metal fencing in the north portion, and asphaltic concrete grindings piles located in the southwestern portion. Gravel surfaces cover portions of the western and northern areas of the property and are utilized for truck and residence parking. Portions of the site not covered by housing/residences, gravel surfaces, and asphaltic concrete grindings piles have a moderate weed/grass growth and the surface soils have a loose consistency. Underground utilities are located within the site. Trees are scattered amongst the residences/living units located in the northeastern portion of the site. The site is relatively level with no major changes in grade.

GEOLOGIC SETTING

The San Joaquin Valley which includes the Manteca area, is a topographic and structural basin that is bounded on the east by the Sierra Nevada Mountains and on the west by the Coast Ranges. The Sierra Nevadas, a fault block dipping gently southwestward, is made up of igneous and metamorphic rocks of pre-Tertiary age that comprise the basement complex beneath the Valley. The Coast Ranges contain folded and faulted sedimentary rocks of Mesozoic and Cenozoic age which are similar to those rocks that underlie the Valley at depth and nonconformably overlie the basement complex; gently dipping to

nearly horizontal sedimentary rocks of Tertiary and Quaternary age overlie the older rocks. These younger rocks are mostly of continental origin and in the Manteca area; they were derived from the Sierra Nevada Mountains.

The Coast Ranges evolved as a result of folding, faulting, and accretion of diverse geologic terrains. They are composed chiefly of sedimentary and metamorphic rocks that are sharply deformed into complex structures. They are broken by numerous faults, the San Andreas Fault being the most notable structural feature.

Both the Sierra Nevada and Coast Ranges are geologically young mountain ranges and possess active and potentially active fault zones. Major active faults and fault zones occur at some distance to the east, west, and south of the Manteca area. The Owens Valley Fault Zone bounds the eastern edge of the Sierra Nevada block and contains both active and potentially active faults.

Portions of the Greenville, Calaveras, and Hayward faults, which are to the west, are considered potentially active. The San Andreas Fault is possibly the best-known fault and is located about 62 miles to the southwest.

There are no active fault traces in the project vicinity. Accordingly, the project area is not within an Earthquake Fault Zone (Special Studies Zone) and will not require a special site investigation by an Engineering Geologist.

Manteca residents could feel the effects of a large seismic event on one of the nearby active or potentially active fault zones. Manteca has experienced groundshaking from earthquakes in the historical past. According to the County Seismic Safety Element, groundshaking of VI intensity (Modified Mercalli Scale) was felt in Manteca from the 1872 Owens Valley Earthquake. This is the largest known earthquake event affecting the Manteca area.

Secondary hazards from earthquakes include rupture, seiche, landslides, liquefaction, and subsidence. Since there are no known faults within the immediate area, ground rupture from surface faulting should not be a potential problem. Seiche and landslides are not hazards in the area either. Liquefaction potential (sudden loss of shear strength in a saturated cohesionless soil) is moderate and is addressed in the liquefaction portion of the site. In addition, there are no known occurrences of structural or architectural damage due to deep subsidence in the Manteca area.

FIELD AND LABORATORY INVESTIGATIONS

Subsurface soil conditions were explored by drilling 8 borings to depths ranging from approximately 10 to 50 feet below existing site grade, using a truck-mounted drill rig. In addition, 2 bulk subgrade samples were obtained from the site for laboratory R-value testing. Furthermore, 6 percolation tests were performed on the site at depths of 3 to 12 feet. The approximate boring, bulk sample, and percolation test locations are shown on the site plan. During drilling operations, penetration tests were performed at regular intervals to evaluate the soil consistency and to obtain information regarding the

engineering properties of the subsoils. Soil samples were retained for laboratory testing. The soils encountered were continuously examined and visually classified in accordance with the Unified Soil Classification System. A more detailed description of the field investigation is presented in Appendix A.

Laboratory tests were performed on selected soil samples to evaluate their physical characteristics and engineering properties. The laboratory-testing program was formulated with emphasis on the evaluation of natural moisture, density, gradation, shear strength, consolidation potential, plasticity, R-value, and moisture-density relationships of the materials encountered. In addition, chemical tests were performed to evaluate the soil-cement reactivity. Details of the laboratory test program and results of the laboratory tests are summarized in Appendix A. This information, along with the field observations, was used to prepare the final boring logs in Appendix A.

SOIL PROFILE AND SUBSURFACE CONDITIONS

Based on our findings, the subsurface conditions encountered appear typical of those found in the geologic region of the site. In general, the surface soils consisted of approximately 6 to 12 inches of very loose silty sand. Some of the borings consisted of approximately 3 inches of gravel at the surface. The surface soils/gravel are disturbed, have low strength characteristics and are highly compressible when saturated.

Below the loose surface soils and gravel, approximately 2 to 3 feet of loose to medium dense silty sand was encountered. Field and laboratory tests suggest that these soils are moderately strong and slightly compressible. Penetration resistance ranged from 6 to 20 blows per foot. Dry densities ranged from 101 to 114 pcf. A representative soil sample consolidated approximately 1¾ percent under a 2 ksf load when saturated. A representative soil sample had an angle of internal friction 33 degrees.

Below approximately 3 to 4 feet, layers of predominately loose to very dense silty sand, sandy silt, silty sand/sandy silt, silty sand/sand, and sand or firm to stiff sandy clay were encountered. Field and laboratory tests suggest that these soils are moderately strong and slightly compressible. Penetration resistance ranged from 5 to 47 blows per foot. Dry densities ranged from 76 to 112 pcf. Representative soil samples consolidated approximately 1¼ to 2 percent under a 2 ksf load when saturated. These soils had similar strength characteristics as the upper soils and extended to the termination depth of our borings.

For additional information about the soils encountered, please refer to the boring logs in Appendix A.

PERCOLATION TESTING

Six percolation tests were performed on the site. The percolation tests were performed at depths of 3 to 12 feet. Results of the tests are as follows:

Test No.	Depth (feet)	Percolation Rate (min/inch)	Soil Type
P1	12	5	Sand (SP)
P2	3	6	Silty Sand (SM)
P3	4	7	Silty Sand (SM)
P4	3	8	Silty Sand (SM)
P5	5	10	Silty Sand (SM)
P6	5.5	10	Silty Sand (SM)

The percolation tests indicate that the soils tested have good absorption characteristics. The percolation rates given are based on 1 inch of fall within a 6-inch diameter hole with a 6- to 12-inch head of water.

GROUNDWATER

Test boring locations were checked for the presence of groundwater during and immediately following the drilling operations. Free groundwater was encountered at approximately 18 feet below existing site grade during our exploratory drilling. Historic high groundwater was estimated to be 4.4 feet based on information obtained from SGMA-well 377966N1212339W001 located within 1.1 miles of the site.

It should be recognized that water table elevations may fluctuate with time, being dependent upon seasonal precipitation, irrigation, land use and climatic conditions, as well as other factors. Therefore, water level observations at the time of the field investigation may vary from those encountered during the construction phase of the project. The evaluation of such factors is beyond the scope of this report.

SOIL LIQUEFACTION

Soil liquefaction is a state of soil particle suspension, caused by a complete loss of strength when the effective stress drops to zero. Liquefaction normally occurs in soils, such as sands, in which the strength is purely frictional. However, liquefaction has occurred in soils other than clean sands. Liquefaction usually occurs under vibratory conditions, such as those induced by seismic events.

To evaluate the liquefaction potential of the site, the following items were evaluated:

- 1) Soil type
- 2) Groundwater depth
- 3) Relative density
- 4) Initial confining pressure
- 5) Intensity and duration of groundshaking

The predominant soils within the project site consist of alternating layers of silty sands, sandy silts, sandy clays, and sands. Free groundwater was encountered at a depth of 18 feet below existing site grade during our exploratory drilling. However, historically groundwater has been as shallow as 4.4 feet within the project site vicinity.

The potential for soil liquefaction during a seismic event was evaluated using the LIQUEFYPRO computer program (version 5.8h) developed by CivilTech Software. For the analysis, a maximum earthquake magnitude of 6.23 was used. A peak horizontal ground surface acceleration of 0.429g was considered conservative and appropriate for the liquefaction analysis. An estimated high groundwater depth of 4.4 feet was used for our analysis. The analysis indicates that soils above a depth of 4.4 feet are non-liquefiable due to the absence of groundwater. The soils below a depth of 4.4 feet have a moderate potential for liquefaction under seismic shaking.

The analysis indicates that the estimated total seismic induced settlement is less than 4 inches. Differential settlement caused by a seismic event is estimated to be less than 2½ inches. The anticipated differential settlement is estimated over a horizontal distance of 100 feet. Accordingly, the liquefaction potential at the site is considered moderate and measures to mitigate liquefaction potential may be required.

CONCLUSIONS AND RECOMMENDATIONS

Based on the findings of our field and laboratory investigations, along with previous geotechnical experience in the project area, the following is a summary of our evaluations, conclusions, and recommendations.

Administrative Summary

In brief, the subject site and soil conditions, with the exception of the loose surface soils, existing development, and estimated settlement associated with the potential for liquefaction, appear to be conducive to the development of the project. The surface soils have a loose consistency. These soils are disturbed, have low strength characteristics and are highly compressible when saturated. Accordingly, it is recommended that the surface soils be recompacted. This compaction effort should stabilize the surface soils and locate any unsuitable or pliant areas not found during our field investigation.

Fill material was not encountered in our borings. However, approximately 45 piles of asphaltic concrete grindings are located in the southwest corner of the site. Furthermore, other fill may be present between and beyond our boring locations. The extent of fill material was determined based on limited test borings and visual observation. Verification of the extent of fill should be determined during site grading. It is recommended that fill soils which have not been properly compacted and certified be excavated and stockpiled so that the native soils can be prepared properly. It is anticipated the fill material will be suitable for reuse as Engineered Fill, provided it is cleansed of excessive organics and debris. The asphaltic concrete grindings should not be used within the planned building pads. The asphalt grindings can be placed within the planned paved areas, provided it is broken into fragments smaller than 4 inches and blended into the fill.

Based on the soil liquefaction analysis performed within the site, the estimated total seismic-induced settlement is less than 4 inches. Differential settlement caused by a seismic event is estimated to be less than $2\frac{2}{3}$ inches. The anticipated differential settlement is estimated over a horizontal distance of 100 feet. The seismic settlements would develop if liquefaction of the underlying saturated subsoils were to occur during a seismic event. If these potential movements are not tolerable, mitigation measures are recommended to reduce structural damage due to soil liquefaction. The project Structural Engineer should evaluate the structure's ability to withstand these potential movements associated with soil liquefaction. If requested, Krazan & Associates, Inc. can provide recommendations for ground improvement to reduce the differential movement associated with seismic loading.

Presently, the site is developed with multiple older residences or living units located on the northern portion of the site. Associated with these developments are buried structures, such as utility lines and irrigation lines that extend into the project site. Demolition activities should include proper removal of any buried structures. Any buried structures, including utilities, encountered during construction should be properly removed and/or relocated. It is suspected that demolition activities of the existing structures will disturb the upper soils. Following demolition activities, the exposed subgrade should be cleaned to firm native ground. The resulting excavation should be backfilled with Engineered Fill, compacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557.

Sandy and gravelly soil conditions were encountered at the site. These cohesionless soils have a tendency to cave in trench wall excavations. Shoring or sloping back trench sidewalls may be required within these sandy and gravelly soils.

Trees are scattered amongst the residences/living units located in the northeastern portion of the site. Tree removal operations should include roots greater than 1 inch in diameter. The resulting excavations should be cleaned to firm native ground and backfilled with Engineered Fill compacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557.

After completion of the recommended site preparation, the site should be suitable for shallow footing support. The proposed structure footings may be designed utilizing an allowable bearing pressure of 2,500 psf for dead-plus-live loads. Footings should have a minimum embedment of 18 inches.

Groundwater Influence on Structures/Construction

During our recent field investigation, groundwater was encountered at a depth of 18 feet. However, historically, groundwater has been encountered at depths as shallow as 4.4 feet below existing site grade. If groundwater is encountered, our firm should be consulted prior to dewatering the site. Installation of a standpipe piezometer is suggested prior to construction should groundwater levels be a concern.

In addition to the groundwater level, if earthwork is performed during or soon after periods of precipitation, the subgrade soils may become saturated, "pump," or not respond to densification techniques. Typical remedial measures include: discing and aerating the soil during dry weather; mixing the soil with dryer materials; removing and replacing the soil with an approved fill material; or mixing

the soil with an approved lime or cement product. Our firm should be consulted prior to implementing remedial measures to observe the unstable subgrade conditions and provide appropriate recommendations.

Site Preparation-General

General site clearing should include removal of vegetation; asphalt; debris; existing utilities; structures including foundations; basement walls and floors; existing stockpiled soil; trees and associated root systems; rubble; rubbish; and any loose and/or saturated materials. Site stripping should extend to a minimum depth of 2 to 4 inches, or until all organics in excess of 3 percent by volume are removed. Deeper stripping may be required in localized areas. These materials will not be suitable for use as Engineered Fill. However, stripped topsoil may be stockpiled and reused in landscape or non-structural areas.

Fill material was not encountered in our borings. However, approximately 45 piles of asphaltic concrete grindings are located in the southwest corner and other fill may be present between and beyond our boring locations. The extent of fill material was determined based on limited test borings and visual observation. Verification of the extent of fill should be determined during site grading. It is recommended that fill soils which have not been properly compacted and certified be excavated and stockpiled so that the native soils can be prepared properly. It is anticipated the fill material will be suitable for reuse as Engineered Fill, provided it is cleansed of excessive organics and debris. Fill intermixed with asphalt concrete grindings should not be used within the planned building pads. The asphalt can be placed within the planned paved areas, provided it is broken into fragments smaller than 4 inches and blended into the fill.

Presently, the site is developed with multiple older residences or living units located on the northern portion of the site. Associated with these developments are buried structures, such as utility lines and irrigation lines that extend into the project site. Demolition activities should include proper removal of any buried structures. Any surface or buried structures, including utilities, encountered during construction should be properly removed and/or relocated. The resulting excavations should be cleaned to firm native ground and backfilled with Engineered Fill, compacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557. Excavations, depressions, or soft and pliant areas extending below planned finish subgrade level should be cleaned to firm undisturbed soil, and backfilled with Engineered Fill. In general, any septic tanks, debris pits, cesspools, or similar structures should be entirely removed. Water wells should be abandoned in accordance with county standards. Concrete footings should be removed to an equivalent depth of at least 3 feet below proposed footing elevations or as recommended by the Soils Engineer. Any other buried structures should be removed in accordance with the recommendations of the Soils Engineer. The resulting excavations should be backfilled with Engineered Fill.

Trees are scattered amongst the residences/living units located in the northeastern portion of the site. Tree removal operations should include roots greater than 1 inch in diameter. The resulting excavations should be cleaned to firm native ground and backfilled with Engineered Fill compacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557.

Following stripping, and demolition activities, the exposed subgrade within the proposed building areas should be excavated to a depth of at least 12 inches below existing subgrade or 12 inches below the bottom of footings, whichever is deeper, worked until uniform and free from large clods, moisture-conditioned to at or above optimum moisture content, and recompacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557. Limits of recompaction should extend 5 feet beyond structural elements. Prior to fill placement, the exposed subgrade soils should be proofrolled and observed by Krazan & Associates, Inc. to verify stability. This compaction effort should stabilize the surface soils and locate any unsuitable or pliant areas not found during our field investigation. Soft or pliant areas should be excavated to firm native ground.

Following stripping and demolition activities, the exposed subgrade within the proposed exterior flatwork and pavement areas should be excavated/scarified to a depth of at least 12 inches, worked until uniform and free from large clods, moisture-conditioned to at or above optimum moisture content, and recompacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557. Limits of recompaction should extend 2 feet beyond flatwork and pavements. Prior to fill placement, the exposed subgrade soils should be proofrolled and observed by Krazan & Associates, Inc. to verify stability. This compaction effort should stabilize the surface soils and locate any unsuitable or pliant areas not found during our field investigation. Soft or pliant areas encountered should be excavated to firm native ground.

It is recommended that any uncertified fill material encountered within pavement areas be removed and/or recompacted. The fill material should be moisture-conditioned to near optimum moisture and recompacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557. As an alternative, the Owner may elect not to recompact the existing fill within paved areas. However, the Owner should be aware that the paved areas may settle which may require annual maintenance. At a minimum, it is recommended that the upper 12 inches of subgrade soil be moisture-conditioned as necessary and recompacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557.

The upper soils, during wet winter months, become very moist due to the absorptive characteristics of the soil. Earthwork operations performed during winter months may encounter very moist unstable soils, which may require removal to grade a stable building foundation. Project site winterization consisting of placement of aggregate base and protecting exposed soils during the construction phase should be performed.

A representative of our firm should be present during all site clearing and grading operations to test and observe earthwork construction. This testing and observation is an integral part of our service as acceptance of earthwork construction is dependent upon compaction of the material and the stability of the material. The Soils Engineer may reject any material that does not meet compaction and stability requirements. Further recommendations of this report are predicated upon the assumption that earthwork construction will conform to recommendations set forth in this section and the Engineered Fill section.

Supplemental Site Preparation - Liquefaction Mitigation - Geogrid

Subsurface soils within the proposed building areas are prone to liquefaction under high ground shaking acceleration during an earthquake. If the proposed structures will be supported on shallow conventional foundations and cannot withstand the potential movements associated with a seismic event mitigation measures will be required. In order to reduce differential settlement associated with seismic settlement, the proposed structure may be constructed over geogrid reinforced Engineered Fill. If this option is utilized, the building area should be excavated to a depth of 6 feet and the resulting excavation should be backfilled with a layered system of Engineered Fill and geogrid reinforcing. The depth of the over-excavation should be measured from existing ground or rough pad grade, whichever is deeper.

The first layer of geogrid reinforcement will be placed directly at the bottom of the excavation. The geogrid material should be overlapped a minimum of 3 feet in all directions. The geogrid strips should be “shingled” such that the exposed geogrid edge is opposite the direction of fill placement (as roof shingles to rain runoff). The interlock between the geogrid and Engineered Fill will provide load transfer. No vehicles may traverse the geogrid prior to placement of the Engineered Fill cover.

The next layer of geogrid should be placed on top of the compacted Engineered Fill. This and subsequent layers need only be overlapped a minimum of 1 foot on all sides. The geogrid strips of this layer, and all subsequent layers within the footprint, should be placed with lengths perpendicular to those in the layer immediately below. The fill soils excavated from the area beneath the structure may be moisture-conditioned and recompacted between geogrid layers as reinforced fill. The reinforced fill should be conditioned to a minimum of 2 percent above optimum moisture content and recompacted to a minimum of 90 percent of maximum density based on ASTM D1557 Test Method.

A total of 5 geogrid layers, including the layer at the base of the excavation, should be installed at vertical increments of 1 foot. The geogrid layers should extend to a minimum of 5 feet beyond the exterior footing perimeter of the structure. The geogrid reinforcement fabric should consist of Tensar® TriAx TX7, NX750, or equivalent. Any additional unstable soils within building areas should be excavated and backfilled with Engineered Fill as requested by the Soil Engineer.

It is recommended that the building site be excavated at once, and soils be stockpiled. The geogrid and excavated soil may then be placed and recompacted as recommended herein. Alternatively, the Contractor may elect to excavate the site in two stages, where excavated soil can be stockpiled over one-half of the site while the other half is mitigated. However, if the Contractor elects the option of two stages over the preferred option of using one stage, a minimum of 5 feet of geogrid from the first half should overlap the second half. Furthermore, the overlapping geogrid should be protected from damages, which may be caused by operating equipment. It is further recommended that flexible utility connections be used for the project.

Engineered Fill

The upper on-site native soils predominately consist of silty sand and silty sand/sandy silt. These soils will be suitable for reuse as Engineered Fill, provided they are cleansed of excessive organics and debris.

The preferred materials specified for Engineered Fill are suitable for most applications with the exception of exposure to erosion. Project site winterization and protection of exposed soils during the construction phase should be the sole responsibility of the Contractor, since he has complete control of the project site at that time.

Imported Fill material should be predominately non-expansive granular material with a plasticity index less than 10 and a UBC Expansion Index less than 15. Imported Fill should be free from rocks and clods greater than 4 inches in diameter. All Imported Fill material should be submitted to the Soils Engineer for approval at least 48 hours prior to delivery at the site.

Percent Passing No. 200 Sieve	20 to 50
Plasticity Index	10 maximum
UBC Standard 29-2 Expansion Index	15 maximum

Fill soils should be placed in lifts approximately 6 inches thick, moisture-conditioned as necessary, and compacted to achieve at least 90 percent maximum density based on ASTM Test Method D1557. Additional lifts should not be placed if the previous lift did not meet the required dry density or if soil conditions are not stable.

Drainage and Landscaping

The ground surface should slope away from building pad and pavement areas toward appropriate drop inlets or other surface drainage devices. In accordance with Section 1804 of the 2022 California Building Code, it is recommended that the ground surface adjacent to foundations be sloped a minimum of 5 percent for a minimum distance of 10 feet away from structures, or to an approved alternative means of drainage conveyance. Swales used for conveyance of drainage and located within 10 feet of foundations should be sloped a minimum of 2 percent. Impervious surfaces, such as pavement and exterior concrete flatwork, within 10 feet of building foundations should be sloped a minimum of 1 percent away from the structure. Drainage gradients should be maintained to carry all surface water to collection facilities and off-site. These grades should be maintained for the life of the project.

Utility Trench Backfill

Utility trenches should be excavated according to accepted engineering practices following OSHA (Occupational Safety and Health Administration) standards by a Contractor experienced in such work. The responsibility for the safety of open trenches should be borne by the Contractor. Traffic and vibration adjacent to trench walls should be reduced; cyclic wetting and drying of excavation side slopes should be avoided. Depending upon the location and depth of some utility trenches, groundwater flow into open excavations could be experienced, especially during or shortly following periods of precipitation.

Sandy soil conditions were encountered at the site. These cohesionless soils have a tendency to cave in trench wall excavations. Shoring or sloping back trench sidewalls may be required within these sandy soils.

Utility trench backfill placed in or adjacent to buildings and exterior slabs should be compacted to at least 90 percent of maximum density based on ASTM Test Method D1557. The utility trench backfill placed in pavement areas should be compacted to at least 90 percent of maximum density based on ASTM Test Method D1557. Pipe bedding should be in accordance with pipe manufacturer's recommendations.

The Contractor is responsible for removing all water-sensitive soils from the trench regardless of the backfill location and compaction requirements. The Contractor should use appropriate equipment and methods to avoid damage to the utilities and/or structures during fill placement and compaction.

Foundations - Conventional

After completion of the recommended site preparation, the site should be suitable for shallow footing support. The proposed structures may be supported on a shallow foundation system bearing on a minimum of 12 inches of Engineered Fill. Spread and continuous footings can be designed for the following maximum allowable soil bearing pressures:

Load	Allowable Loading
Dead Load Only	1,875 psf
Dead-Plus-Live Load	2,500 psf
Total Load, including wind or seismic loads	3,325 psf

The footings should have a minimum embedment depth of 18 inches below pad subgrade (soil grade) or adjacent exterior grade, whichever is lower. Footings should have a minimum width of 12 inches, regardless of load.

The footing excavations should not be allowed to dry out any time prior to pouring concrete. It is recommended that footings be reinforced by at least one No. 4 reinforcing bar in both top and bottom.

The total settlement caused by static loads is not expected to exceed 1 inch. Differential settlement associated with static loads should be less than ½ inch. Most of the movement is expected to occur during construction as the loads are applied. However, additional post-construction movement may occur if the foundation soils are flooded or saturated.

The total and differential seismic-induced settlement is estimated to be less than 4 inches and 2⅔ inches, respectively. If the structure is supported on geogrid reinforced soil, the differential settlement associated with a seismic event is estimated to be less than 1 inch. The anticipated differential settlement is estimated over a horizontal distance of 100 feet. The seismic settlements would develop if liquefaction of the underlying saturated sandy soils were to occur during a seismic event.

Resistance to lateral footing displacement can be computed using an allowable friction factor of 0.4 acting between the base of foundations and the supporting subgrade. Lateral resistance for footings can alternatively be developed using an equivalent fluid passive pressure of 350 pounds per cubic foot acting against the appropriate vertical footing faces. The frictional and passive resistance of the soil may be combined without reduction in determining the total lateral resistance. A $\frac{1}{3}$ increase in the above value may be used for short duration, wind, or seismic loads.

Floor Slabs and Exterior Flatwork

In areas where moisture-sensitive floor coverings will be included, concrete slab-on-grade floors should be underlain by a water vapor retarder. The water vapor retarder should be installed in accordance with accepted engineering practice. The water vapor retarder should consist of a vapor retarder sheeting underlain by a minimum of 3 inches of compacted, clean, gravel of $\frac{3}{4}$ -inch maximum size. To aid in concrete curing an optional 2 to 4 inches of granular fill may be placed on top of the vapor retarder. The granular fill should consist of damp clean sand with at least 10 to 30 percent of the sand passing the 100 sieve. The sand should be free of clay, silt, or organic material. Rock dust which is manufactured sand from rock crushing operations is typically suitable for the granular fill. This granular fill material should be compacted.

The floor slab should be reinforced at a minimum with #3 reinforcement bars at 18 inches on-center each way within the middle one-third. Thicker floor slabs with increased concrete strength and reinforcement should be designed wherever heavy concentrated loads, heavy equipment, or machinery is anticipated.

The exterior floors should be poured separately in order to act independently of the walls and foundation system. All fills required to bring the building pads to grade should be Engineered Fills.

Moisture within the structure may be derived from water vapors, which were transformed from the moisture within the soils. This moisture vapor can travel through the vapor membrane and penetrate the slab-on-grade. This moisture vapor penetration can affect floor coverings and produce mold and mildew in the structure. To reduce moisture vapor intrusion, it is recommended that a vapor retarder be installed. It is recommended that the utility trenches within the structure be compacted, as specified in our report, to reduce the transmission of moisture through the utility trench backfill. Special attention to the immediate drainage and irrigation around the building is recommended. Positive drainage should be established away from the structure and should be maintained throughout the life of the structure. Ponding of water should not be allowed adjacent to the structure. Over-irrigation within landscaped areas adjacent to the structure should not be performed. In addition, ventilation of the structure (i.e. ventilation fans) is recommended to reduce the accumulation of interior moisture.

Lateral Earth Pressures and Retaining Walls

Walls retaining horizontal backfill and capable of deflecting a minimum of 0.1 percent of its height at the top may be designed using an equivalent fluid active pressure of 31 pounds per square foot per foot of depth. Walls that are incapable of this deflection or walls that are fully constrained against deflection may be designed for an equivalent fluid at-rest pressure of 52 pounds per square foot per foot per depth. Expansive soils should not be used for backfill against walls. The wedge of non-expansive backfill

material should extend from the bottom of each retaining wall outward and upward at a slope of 2:1 (horizontal to vertical) or flatter. The stated lateral earth pressures do not include the effects of hydrostatic water pressures generated by infiltrating surface water that may accumulate behind the retaining walls; or loads imposed by construction equipment, foundations, or roadways.

Retaining and/or below grade walls should be drained with either perforated pipe encased in free-draining gravel or a prefabricated drainage system. The gravel zone should have a minimum width of 12 inches and should extend upward to within 12 inches of the top of the wall. The upper 12 inches of backfill should consist of native soils, concrete, asphaltic concrete, or other suitable backfill to reduce surface drainage into the wall drain system. The aggregate should conform to Class 2 permeable materials graded in accordance with CalTrans Standard Specifications (2024). Prefabricated drainage systems, such as Miradrain®, Enkadrain®, or an equivalent substitute, are acceptable alternatives in lieu of gravel, provided they are installed in accordance with the manufacturer's recommendations. If a prefabricated drainage system is proposed, our firm should review the system for final acceptance prior to installation.

Drainage pipes should be placed with perforations down and should discharge in a non-erosive manner away from foundations and other improvements. The pipes should be placed no higher than 6 inches above the heel of the wall, in the center line of the drainage blanket and should have a minimum diameter of four inches. Collector pipes may be either slotted or perforated. Slots should be no wider than 1/8 inch in diameter, while perforations should be no more than 1/4 inch in diameter. If retaining walls are less than 6 feet in height, the perforated pipe may be omitted in lieu of weep holes on 4 feet maximum spacing. The weep holes should consist of 4-inch diameter holes (concrete walls) or unmortared head joints (masonry walls) and not be higher than 18 inches above the lowest adjacent grade. Two 8-inch square overlapping patches of geotextile fabric (conforming to CalTrans Standard Specifications for "edge drains") should be affixed to the rear wall opening of each weep hole to retard soil piping.

During grading and backfilling operations adjacent to any walls, heavy equipment should not be allowed to operate within a lateral distance of 5 feet from the wall or within a lateral distance equal to the wall height, whichever is greater, to avoid developing excessive lateral pressures. Within this zone, only hand operated equipment ("whackers," vibratory plates, or pneumatic compactors) should be used to compact the backfill soils.

R-Value Test Results and Pavement Design

Two subgrade soil samples were obtained from the project site for R-value testing at the locations shown on the attached site plan. The samples were tested in accordance with the State of California Materials Manual Test Designation 301. The results of the tests are as follows:

Sample	Depth	Description	R-Value at Equilibrium
1	12-24"	Silty Sand (SM)	59
2	12-24"	Silty Sand (SM)	58

The test results are moderate and indicate good subgrade support characteristics under dynamic traffic loads. The following table shows the recommended pavement sections for various traffic indices.

Traffic Index	Asphaltic Concrete	Class II Aggregate Base*	Compacted Subgrade**
4.0	2.0"	4.0"	12.0"
4.5	2.5"	4.0"	12.0"
5.0	2.5"	4.0"	12.0"
5.5	3.0"	4.0"	12.0"
6.0	3.0"	4.0"	12.0"
6.5	3.5"	4.0"	12.0"
7.0	4.0"	4.0"	12.0"
7.5	4.0"	4.0"	12.0"

* 95% compaction based on ASTM Test Method D1557 or CAL 216

** 90% compaction based on ASTM Test Method D1557 or CAL 216

If traffic indices are not available, an estimated (typical value) index of 4.5 may be used for light automobile traffic, and an index of 7.0 may be used for light truck traffic.

The following recommendations are for light-duty and heavy-duty Portland Cement Concrete Pavement Sections based on the design procedures developed by the Portland Cement Association.

PORTLAND CEMENT PAVEMENT LIGHT DUTY

Traffic Index	Portland Cement Concrete***	Class II Aggregate Base*	Compacted Subgrade**
4.5	5.0"	--	12.0"

HEAVY DUTY

Traffic Index	Portland Cement Concrete***	Class II Aggregate Base*	Compacted Subgrade**
7.0	6.5"	--	12.0"

* 95% compaction based on ASTM Test Method D1557 or CAL 216

** 90% compaction based on ASTM Test Method D1557 or CAL 216

***Minimum compressive strength of 3000 psi

It is recommended that any uncertified fill material encountered within pavement areas be removed and/or recompacted. The fill material should be moisture-conditioned to near optimum moisture and recompacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557. As an alternative, the Owner may elect not to recompact the existing fill within paved areas. However, the Owner should be aware that the paved areas may settle which may require annual maintenance. At a minimum, it is recommended that the upper 12 inches of subgrade soil be moisture-conditioned as necessary and recompacted to a minimum of 90 percent of maximum density based on ASTM Test Method D1557.

Seismic Parameters – 2022 California Building Code

The Site Class per Section 1613 of the 2022 California Building Code (2022 CBC) and ASCE 7-16, Chapter 20 is based upon the site soil conditions. It is our opinion that a Site Class D is most consistent with the subject site soil conditions. For seismic design of the structures based on the seismic provisions of the 2022 CBC, we recommend the following parameters:

Seismic Item	Value	CBC Reference
Site Class	D	Section 1613.2.2
Site Coefficient F_a	1.173	Table 1613.2.3 (1)
S_s	0.817	Section 1613.2.1
S_{MS}	0.959	Section 1613.2.3
S_{DS}	0.639	Section 1613.2.4
Site Coefficient F_v	1.993	Table 1613.2.3 (2)
S_1	0.307	Section 1613.2.1
S_{M1}	0.612	Section 1613.2.3
S_{D1}	0.408	Section 1613.2.4
T_s	0.638	Section 1613.2

* Based on Equivalent Lateral Force (ELF) Design Procedure being used.

Soil Cement Reactivity

Excessive sulfate in either the soil or native water may result in an adverse reaction between the cement in concrete (or stucco) and the soil. HUD/FHA and UBC have developed criteria for evaluation of sulfate levels and how they relate to cement reactivity with soil and/or water.

Soil samples were obtained from the site and tested in accordance with State of California Materials Manual Test Designation 417. The sulfate concentrations detected from these soil samples were less than 150 ppm (1.7 ppm) and are below the maximum allowable values established by HUD/FHA and UBC. Therefore, no special design requirements are necessary to compensate for sulfate reactivity with the cement.

Compacted Material Acceptance

Compaction specifications are not the only criteria for acceptance of the site grading or other such activities. However, the compaction test is the most universally recognized test method for assessing the performance of the Grading Contractor. The numerical test results from the compaction test cannot be used to predict the engineering performance of the compacted material. Therefore, the acceptance of compacted materials will also be dependent on the stability of that material. The Soils Engineer has the option of rejecting any compacted material regardless of the degree of compaction if that material is considered to be unstable or if future instability is suspected. A specific example of rejection of fill

material passing the required percent compaction is a fill which has been compacted with an in-situ moisture content significantly less than optimum moisture. This type of dry fill (brittle fill) is susceptible to future settlement if it becomes saturated or flooded.

Testing and Inspection

A representative of Krazan & Associates, Inc. should be present at the site during the earthwork activities to confirm that actual subsurface conditions are consistent with the exploratory fieldwork. This activity is an integral part of our service, as acceptance of earthwork construction is dependent upon compaction testing and stability of the material. This representative can also verify that the intent of these recommendations is incorporated into the project design and construction. Krazan & Associates, Inc. will not be responsible for grades or staking, since this is the responsibility of the Prime Contractor.

LIMITATIONS

Soils Engineering is one of the newest divisions of Civil Engineering. This branch of Civil Engineering is constantly improving as new technologies and understanding of earth sciences advance. Although your site was analyzed using the most appropriate and most current techniques and methods, undoubtedly there will be substantial future improvements in this branch of engineering. In addition to advancements in the field of Soils Engineering, physical changes in the site, either due to excavation or fill placement, new agency regulations, or possible changes in the proposed structure after the soils report is completed may require the soils report to be professionally reviewed. In light of this, the Owner should be aware that there is a practical limit to the usefulness of this report without critical review. Although the time limit for this review is strictly arbitrary, it is suggested that 2 years be considered a reasonable time for the usefulness of this report.

Foundation and earthwork construction is characterized by the presence of a calculated risk that soil and groundwater conditions have been fully revealed by the original foundation investigation. This risk is derived from the practical necessity of basing interpretations and design conclusions on limited sampling of the earth. The recommendations made in this report are based on the assumption that soil conditions do not vary significantly from those disclosed during our field investigation. If any variations or undesirable conditions are encountered during construction, the Soils Engineer should be notified so that supplemental recommendations may be made.

The conclusions of this report are based on the information provided regarding the proposed construction. If the proposed construction is relocated or redesigned, the conclusions in this report may not be valid. The Soils Engineer should be notified of any changes so the recommendations may be reviewed and re-evaluated.

This report is a Geotechnical Engineering Investigation with the purpose of evaluating the soil conditions in terms of foundation design. The scope of our services did not include any Environmental Site Assessment for the presence or absence of hazardous and/or toxic materials in the soil, groundwater, or atmosphere; or the presence of wetlands. Any statements, or absence of statements, in this report or


on any boring log regarding odors, unusual or suspicious items, or conditions observed, are strictly for descriptive purposes and are not intended to convey engineering judgment regarding potential hazardous and/or toxic assessment.

The geotechnical engineering information presented herein is based upon professional interpretation utilizing standard engineering practices and a degree of conservatism deemed proper for this project. It is not warranted that such information and interpretation cannot be superseded by future geotechnical engineering developments. We emphasize that this report is valid for the project outlined above and should not be used for any other sites.

If you have any questions or if we may be of further assistance, please do not hesitate to contact our office at (209) 572-2200.

Respectfully submitted,
KRAZAN & ASSOCIATES, INC.


Wayne Andrade
Project Geologist


David R. Jarosz, II
Managing Engineer
RGE No. 2698/RCE No. 60185



WA/DRJ:ht

APPENDIX A
FIELD AND LABORATORY INVESTIGATIONS

Field Investigation

The field investigation consisted of a surface reconnaissance and a subsurface exploratory program. Eight 4½-inch to 6½-inch exploratory borings were advanced. The boring locations are shown on the site plan.

The soils encountered were logged in the field during the exploration and, with supplementary laboratory test data, are described in accordance with the Unified Soil Classification System.

Modified standard penetration tests and standard penetration tests were performed at selected depths. These tests represent the resistance to driving a 2½-inch and 1½-inch diameter split barrel sampler, respectively. The driving energy was provided by a hammer weighing 140 pounds falling 30 inches. Relatively undisturbed soil samples were obtained while performing this test. Bag samples of the disturbed soil were obtained from the auger cuttings. The modified standard penetration tests are identified in the sample type on the boring logs with a full shaded in block. The standard penetration tests are identified in the sample type on the boring logs with half of the block shaded. All samples were returned to our Clovis laboratory for evaluation.

Laboratory Investigation

The laboratory investigation was programmed to determine the physical and mechanical properties of the foundation soil underlying the site. Test results were used as criteria for determining the engineering suitability of the surface and subsurface materials encountered.

In-situ moisture content, dry density, consolidation, direct shear, and sieve analysis tests were completed for the undisturbed samples representative of the subsurface material. Atterberg limits and R-value tests were completed for select bag samples obtained from the auger cuttings. These tests, supplemented by visual observation, comprised the basis for our evaluation of the site material.


The logs of the exploratory borings and laboratory determinations are presented in this Appendix.

UNIFIED SOIL CLASSIFICATION SYSTEM

UNIFIED SOIL CLASSIFICATION AND SYMBOL CHART			
COARSE-GRAINED SOILS (more than 50% of material is larger than No. 200 sieve size.)			
GRAVELS More than 50% of coarse fraction larger than No. 4 sieve size	Clean Gravels (Less than 5% fines)		
		GW	Well-graded gravels, gravel-sand mixtures, little or no fines
		GP	Poorly-graded gravels, gravel-sand mixtures, little or no fines
	Gravels with fines (More than 12% fines)		
		GM	Silty gravels, gravel-sand-silt mixtures
		GC	Clayey gravels, gravel-sand-clay mixtures
SANDS 50% or more of coarse fraction smaller than No. 4 sieve size	Clean Sands (Less than 5% fines)		
		SW	Well-graded sands, gravelly sands, little or no fines
		SP	Poorly graded sands, gravelly sands, little or no fines
	Sands with fines (More than 12% fines)		
		SM	Silty sands, sand-silt mixtures
SILTS AND CLAYS Liquid limit less than 50%	FINE-GRAINED SOILS (50% or more of material is smaller than No. 200 sieve size.)		
		ML	Inorganic silts and very fine sands, rock flour, silty of clayey fine sands or clayey silts with slight plasticity
		CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays
		OL	Organic silts and organic silty clays of low plasticity
		MH	Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts
		CH	Inorganic clays of high plasticity, fat clays
		OH	Organic clays of medium to high plasticity, organic silts
		PT	Peat and other highly organic soils
	HIGHLY ORGANIC SOILS		
		PT	Peat and other highly organic soils

CONSISTENCY CLASSIFICATION	
Description	Blows per Foot
<i>Granular Soils</i>	
Very Loose	< 5
Loose	5 – 15
Medium Dense	16 – 40
Dense	41 – 65
Very Dense	> 65
<i>Cohesive Soils</i>	
Very Soft	< 3
Soft	3 – 5
Firm	6 – 10
Stiff	11 – 20
Very Stiff	21 – 40
Hard	> 40

GRAIN SIZE CLASSIFICATION		
Grain Type	Standard Sieve Size	Grain Size in Millimeters
Boulders	Above 12 inches	Above 305
Cobbles	12 to 13 inches	305 to 76.2
Gravel	3 inches to No. 4	76.2 to 4.76
Coarse-grained	3 to ¾ inches	76.2 to 19.1
Fine-grained	¾ inches to No. 4	19.1 to 4.76
Sand	No. 4 to No. 200	4.76 to 0.074
Coarse-grained	No. 4 to No. 10	4.76 to 2.00
Medium-grained	No. 10 to No. 40	2.00 to 0.42
Fine-grained	No. 40 to No. 200	0.42 to 0.074
Silt and Clay	Below No. 200	Below 0.074



Log of Boring B1

Project: Apartment and Retail Buildings

Project No: 072-25004

Client: MCR Engineering

Figure No.: A-1

Location: 2218 W. Yosemite Avenue, Manteca, California

Logged By: Emmett Gonzales

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)			
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	20	40	60	10	20	30	40
0		Ground Surface											
		GRAVEL = 3 inches											
		SILTY SAND (SM)											
		Very loose, fine-grained; brown, moist, drills easily											
2		Loose below 12 inches	108.9	6.1		6							
4													
6			111.4	6.0		10							
8		SILTY SAND/SAND (SM/SP)											
		Loose, fine-grained; light brown, damp, drills easily											
10			101.1	3.8		13							
12													
14													
16		End of Borehole											
18													
20													

Drill Method: Solid Flight

Drill Date: 2-18-25

Drill Rig: CME 55-2

Krazan and Associates

Hole Size: 4½ Inches

Driller: Eddie Tapia

Elevation: 15 Feet

Sheet: 1 of 1

Log of Boring B2

Project: Apartment and Retail Buildings

Project No: 072-25004

Client: MCR Engineering

Figure No.: A-2

Location: 2218 W. Yosemite Avenue, Manteca, California

Logged By: Emmett Gonzales

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)				
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.								
							20	40	60	10	20	30	40	
0		Ground Surface												
		SILTY SAND (SM) Very loose, fine-grained; dark brown, moist, drills easily Loose below 12 inches												
2			113.9	9.6		10								
4														
		Brown below 5 feet												
6			112.3	7.9		6								
8														
		SILTY SAND/SAND (SM/SP) Loose, fine- to medium-grained; light brown, moist, drills easily												
10			111.0	7.5		13								
12														
14														
16		End of Borehole												
18														
20														

Drill Method: Solid Flight

Drill Date: 2-18-25

Drill Rig: CME 55-2

Krazan and Associates

Hole Size: 4½ Inches

Driller: Eddie Tapia

Elevation: 15 Feet

Sheet: 1 of 1

Log of Boring B3

Project: Apartment and Retail Buildings

Project No: 072-25004

Client: MCR Engineering

Figure No.: A-3

Location: 2218 W. Yosemite Avenue, Manteca, California

Logged By: Emmett Gonzales

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)			
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	20	40	60	10	20	30	40
0		Ground Surface											
		GRAVEL = 3 inches											
		SILTY SAND (SM)											
		Very loose, fine-grained; brown, damp, drills easily											
2		Loose below 12 inches	113.5	4.7		7							
4													
6			108.8	4.8		12							
8													
10		End of Borehole											
12													
14													
16													
18													
20													

Drill Method: Solid Flight

Drill Date: 2-18-25

Drill Rig: CME 55-2

Krazan and Associates

Hole Size: 4½ Inches

Driller: Eddie Tapia

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B4

Project: Apartment and Retail Buildings

Project No: 072-25004

Client: MCR Engineering

Figure No.: A-4

Location: 2218 W. Yosemite Avenue, Manteca, California

Logged By: Emmett Gonzales

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)			
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	20	40	60	10	20	30	40
0		Ground Surface											
0		GRAVEL = 3 inches											
2		SILTY SAND (SM) Very loose, fine-grained; brown, damp, drills easily Loose below 12 inches	108.9	5.8		7							
4													
6			111.1	3.3		10							
8													
10		End of Borehole											
12													
14													
16													
18													
20													

Drill Method: Solid Flight

Drill Date: 2-18-25

Drill Rig: CME 55-2

Krazan and Associates

Hole Size: 4½ Inches

Driller: Eddie Tapia

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B5

Project: Apartment and Retail Buildings

Project No: 072-25004

Client: MCR Engineering

Figure No.: A-5

Location: 2218 W. Yosemite Avenue, Manteca, California

Logged By: Emmett Gonzales

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)			
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.	20	40	60	10	20	30	40
0		Ground Surface											
2		SILTY SAND (SM) Very loose, fine-grained; brown, moist, drills easily Loose below 12 inches	107.0	7.8		8							
4		SILTY SAND/SANDY SILT (SM/ML) Medium dense, fine- to medium-grained; reddish-brown, moist, drills easily	99.0	13.7		19							
8		SAND (SP) Loose, fine- to medium-grained; light brown, damp, drills easily											
10			109.1	3.3		10							
12													
14													
16		End of Borehole											
18													
20													

Drill Method: Solid Flight

Drill Date: 2-18-25

Drill Rig: CME 55-2

Krazan and Associates

Hole Size: 4½ Inches

Driller: Eddie Tapia

Elevation: 15 Feet

Sheet: 1 of 1

Log of Boring B6

Project: Apartment and Retail Buildings

Project No: 072-25004

Client: MCR Engineering

Figure No.: A-6

Location: 2218 W. Yosemite Avenue, Manteca, California

Logged By: Emmett Gonzales

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)			
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.							
0		Ground Surface					20	40	60	10	20	30	40
0		SILTY SAND (SM) Very loose, fine-grained; brown, moist, drills easily											
2		Loose below 12 inches	106.4	6.2		8							
4		Medium dense below 5 feet											
6			102.0	2.0		21							
8		End of Borehole											
10													
12													
14													
16													
18													
20													

Drill Method: Solid Flight

Drill Date: 2-18-25

Drill Rig: CME 55-2

Krazan and Associates

Hole Size: 4½ Inches

Driller: Eddie Tapia

Elevation: 10 Feet

Sheet: 1 of 1

Log of Boring B7

Project: Apartment and Retail Buildings

Project No: 072-25004

Client: MCR Engineering

Figure No.: A-7

Location: 2218 W. Yosemite Avenue, Manteca, California

Logged By: Emmett Gonzales

Depth to Water>

Initial: 18½ Feet

At Completion: 18 Feet

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft	Water Content (%)			
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.					
		Ground Surface						20	40	60	10 20 30 40
0		SILTY SAND (SM) Very loose, fine-grained; brown, damp, drills easily									
2		Loose below 12 inches	101.3	5.1		14					
4											
6			107.9	4.9		11					
8		Medium dense below 8 feet									
10			104.0	12.1		10					
12											
14		SAND (SP) Medium dense, fine-grained; brown, moist, drills easily									
16			110.0	10.9		11					
18											
20		SANDY CLAY (CL) Stiff, fine-grained; gray/brown, saturated, drills easily									

Drill Method: Hollow Stem

Drill Date: 2-18-25

Drill Rig: CME 55-2

Krazan and Associates

Hole Size: 6½ Inches

Driller: Eddie Tapia

Elevation: 50 Feet

Sheet: 1 of 3

Log of Boring B7

Project: Apartment and Retail Buildings

Project No: 072-25004

Client: MCR Engineering

Figure No.: A-7


Location: 2218 W. Yosemite Avenue, Manteca, California

Logged By: Emmett Gonzales

Depth to Water>

Initial: 18½ Feet

At Completion: 18 Feet



Drill Method: Hollow Stem

Drill Date: 2-18-25

Drill Rig: CME 55-2

Krazan and Associates

Hole Size: 6½ Inches

Driller: Eddie Tapia

Elevation: 50 Feet

Sheet: 2 of 3

Log of Boring B7

Project: Apartment and Retail Buildings

Project No: 072-25004

Client: MCR Engineering

Figure No.: A-7

Location: 2218 W. Yosemite Avenue, Manteca, California

Logged By: Emmett Gonzales

Depth to Water>

Initial: 18½ Feet

At Completion: 18 Feet

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft	Water Content (%)
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.		
42		Very dense and fine- to medium-grained with trace GRAVEL below 45 feet	101.0	13.9		38		
44								
46			110.7	13.9		47		
48		End of Borehole						
50								
52								
54								
56								
58								
60								

Drill Method: Hollow Stem

Drill Date: 2-18-25

Drill Rig: CME 55-2

Krazan and Associates

Hole Size: 6½ Inches

Driller: Eddie Tapia

Elevation: 50 Feet

Sheet: 3 of 3

Log of Boring B8

Project: Apartment and Retail Buildings

Project No: 072-25004

Client: MCR Engineering

Figure No.: A-8

Location: 2218 W. Yosemite Avenue, Manteca, California

Logged By: Emmett Gonzales

Depth to Water>

Initial: None

At Completion: None

SUBSURFACE PROFILE			SAMPLE				Penetration Test blows/ft			Water Content (%)				
Depth (ft)	Symbol	Description	Dry Density (pcf)	Moisture (%)	Type	Blows/ft.								
							20	40	60	10	20	30	40	
0		Ground Surface												
		SILTY SAND (SM) Very loose, fine-grained; brown, damp, drills easily Medium dense below 12 inches												
2														
4														
		Loose below 5 feet												
6			110.1	2.8		15								
8														
10														
		End of Borehole												
12														
14														
16														
18														
20														

Drill Method: Solid Flight

Drill Date: 2-18-25

Drill Rig: CME 55-2

Krazan and Associates

Hole Size: 4½ Inches


Driller: Eddie Tapia

Elevation: 10 Feet

Sheet: 1 of 1


Consolidation Test

Project No	Boring No. & Depth	Date	Soil Classification
072-25004	B1 @ 2-3'	3/11/2025	SM




Consolidation Test

Project No	Boring No. & Depth	Date	Soil Classification
072-25004	B1 @ 5-6'	3/11/2025	SM




Consolidation Test

Project No	Boring No. & Depth	Date	Soil Classification
072-25004	B2 @ 5-6'	3/11/2025	SM




Shear Strength Diagram (Direct Shear)
ASTM D - 3080 / AASHTO T - 236

Project Number	Boring No. & Depth	Soil Type	Date
072-25004	B5 @ 2-3'	SM	3/11/2025



Grain Size Analysis



Project Name

Apartment and Retail Building

Project Number

072-25004

Soil Classification

SM

Sample Number

B1 @ 2-3'

Gravel

Fine

Coarse

Sand


Medium

Fine

Silt or Clay

Krazan Testing Laboratory

Grain Size Analysis



Gravel		Sand			Silt or Clay
Coarse	Fine	Coarse	Medium	Fine	

(Unified Soils Classification)

Project Name

Project Number

Soil Classification

Sample Number

Apartment and Retail Building

072-25004

SM

B2 @ 5-6'

Plasticity Index of Soils

ASTM D4318/AASHTO T89 T90/CT 204

Project: **Apartment and Retail Building**
 Project Number: **072-25004**
 Date Sampled: 2/18/2025
 Sampled By: EG
 Sample Number: -
 Sample Location: B7 @ 20-21'
 Sample Description: CL


Date Tested: 2/25/2025
 Tested By: JM
 Verified By: JG

Trial Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare (g)	44.26	41.19		44.25	43.17	
Weight of Dry Soil & Tare (g)	41.75	39.20		40.18	39.44	
Weight of Tare (g)	28.97	28.93		28.66	28.69	
Weight of water (g)	2.51	1.99		4.07	3.73	
Weight of Dry Soil (g)	12.78	10.27		11.52	10.75	
Water Content (% of dry wt.)	19.6%	19.4%		35.3%	34.7%	
Number of Blows				25	25	

Plastic Limit : 20

Liquid Limit : 35

Plasticity Index : 15
 Unified Soil Classification : CL
 Requirement:
 Approx. % of Material Retained on # 40 Sieve:



Departures from Outlined Procedure:

Unusual Conditions, Other Notes:

Plasticity Index of Soils

ASTM D4318/AASHTO T89 T90/CT 204

Project: **Apartment and Retail Building**
 Project Number: **072-25004**
 Date Sampled: 2/18/2025
 Sampled By: EG
 Sample Number: -
 Sample Location: B7 @ 25-26'
 Sample Description: CL



Date Tested: 2/25/2025
 Tested By: JM
 Verified By: JG

Trial Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare (g)	43.16	40.84		45.39	46.25	
Weight of Dry Soil & Tare (g)	40.74	38.81		41.40	42.10	
Weight of Tare (g)	28.97	28.93		28.64	28.68	
Weight of water (g)	2.42	2.03		3.99	4.15	
Weight of Dry Soil (g)	11.77	9.88		12.76	13.42	
Water Content (% of dry wt.)	20.6%	20.5%		31.3%	30.9%	
Number of Blows				25	25	

Plastic Limit : 21

Liquid Limit : 31

Plasticity Index : 10
 Unified Soil Classification : CL
 Requirement:
 Approx. % of Material Retained on # 40 Sieve:



Departures from Outlined Procedure:

Unusual Conditions, Other Notes:

Plasticity Index of Soils

ASTM D4318/AASHTO T89 T90/CT 204

Project: **Apartment and Retail Building**
 Project Number: **072-25004**
 Date Sampled: 2/18/2025
 Sampled By: EG
 Sample Number: -
 Sample Location: B7 @ 30-31'
 Sample Description: ML


Date Tested: 2/25/2025
 Tested By: JM
 Verified By: JG

Trial Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare (g)						
Weight of Dry Soil & Tare (g)						
Weight of Tare (g)						
Weight of water (g)						
Weight of Dry Soil (g)						
Water Content (% of dry wt.)						
Number of Blows						

Plastic Limit : N/D

Liquid Limit : N/D

Plasticity Index : **NON-PLASTIC**
 Unified Soil Classification : **NON-PLASTIC**
 Requirement:
 Approx. % of Material Retained on # 40 Sieve:



Departures from Outlined Procedure:

Unusual Conditions, Other Notes:

Plasticity Index of Soils

ASTM D4318/AASHTO T89 T90/CT 204

Project: **Apartment and Retail Building**

Project Number: **072-25004**

Date Sampled: 2/18/2025

Sampled By: EG

Sample Number: -

Sample Location: B7 @ 35-36'

Sample Description: SM

Date Tested: 2/25/2025

Tested By: JM

Verified By: JG

Trial Number	Plastic Limit			Liquid Limit		
	1	2	3	1	2	3
Weight of Wet Soil & Tare (g)						
Weight of Dry Soil & Tare (g)						
Weight of Tare (g)						
Weight of water (g)						
Weight of Dry Soil (g)						
Water Content (% of dry wt.)						
Number of Blows						

Plastic Limit : N/D



Liquid Limit : N/D

Plasticity Index : NON-PLASTIC

Unified Soil Classification : NON-PLASTIC

Requirement:

Approx. % of Material Retained on # 40 Sieve:



Departures from Outlined Procedure:


Unusual Conditions, Other Notes:

R - VALUE TEST ASTM D - 2844 / CAL 301

Project Number : 072-25004
Project Name : Apartment and Retail Building
Date : 3/4/2025
Sample Location/Curve Number : RV#1
Soil Classification : SM

TEST	A	B	C
Percent Moisture @ Compaction, %	10.1	9.3	8.6
Dry Density, lbm/cu.ft.	118.8	119.7	119.8
Exudation Pressure, psi	180	300	610
Expansion Pressure, (Dial Reading)	0	0	0
Expansion Pressure, psf	0	0	0
Resistance Value R	55	59	65

R Value at 300 PSI Exudation Pressure	59
R Value by Expansion Pressure (TI =): 5	Expansion Pressure nil




R - VALUE TEST ASTM D - 2844 / CAL 301

Project Number : 072-25004
 Project Name : Apartment and Retail Building
 Date : 3/4/2025
 Sample Location/Curve Number : RV#2
 Soil Classification : SM

TEST	A	B	C
Percent Moisture @ Compaction, %	10.7	10.0	9.3
Dry Density, lbm/cu.ft.	116.4	117.1	118.1
Exudation Pressure, psi	130	300	560
Expansion Pressure, (Dial Reading)	0	0	0
Expansion Pressure, psf	0	0	0
Resistance Value R	52	58	64

R Value at 300 PSI Exudation Pressure	58
R Value by Expansion Pressure (TI =): 5	Expansion Pressure nil



APPENDIX B

EARTHWORK SPECIFICATIONS

GENERAL

When the text of the report conflicts with the general specifications in this appendix, the recommendations in the report have precedence.

SCOPE OF WORK: These specifications and applicable plans pertain to and include all earthwork associated with the site rough grading, including but not limited to the furnishing of all labor, tools, and equipment necessary for site clearing and grubbing, stripping, preparation of foundation materials for receiving fill, excavation, processing, placement and compaction of fill and backfill materials to the lines and grades shown on the project grading plans, and disposal of excess materials.

PERFORMANCE: The Contractor shall be responsible for the satisfactory completion of all earthwork in accordance with the project plans and specifications. This work shall be inspected and tested by a representative of Krazan and Associates, Inc., hereinafter known as the Soils Engineer and/or Testing Agency. Attainment of design grades when achieved shall be certified by the project Civil Engineer. Both the Soils Engineer and the Civil Engineer are the Owner's representatives. If the Contractor should fail to meet the technical or design requirements embodied in this document and on the applicable plans, he shall make the necessary readjustments until all work is deemed satisfactory as determined by both the Soils Engineer and the Civil Engineer. No deviation from these specifications shall be made except upon written approval of the Soils Engineer, Civil Engineer or project Architect.

No earthwork shall be performed without the physical presence or approval of the Soils Engineer. The Contractor shall notify the Soils Engineer at least 2 working days prior to the commencement of any aspect of the site earthwork.

The Contractor agrees that he shall assume sole and complete responsibility for job site conditions during the course of construction of this project, including safety of all persons and property; that this requirement shall apply continuously and not be limited to normal working hours; and that the Contractor shall defend, indemnify and hold the Owner and the Engineers harmless from any and all liability, real or alleged, in connection with the performance of work on this project, except for liability arising from the sole negligence of the Owner or the Engineers.

TECHNICAL REQUIREMENTS: All compacted materials shall be densified to a density not less than 90 percent relative compaction based on ASTM Test Method D1557 or CAL-216, as specified in the technical portion of the Soil Engineer's report. The location and frequency of field density tests shall be as determined by the Soils Engineer. The results of these tests and compliance with these specifications shall be the basis upon which satisfactory completion of work will be judged by the Soils Engineer.

SOILS AND FOUNDATION CONDITIONS: The Contractor is presumed to have visited the site and to have familiarized himself with existing site conditions and the contents of the data presented in the soil report.

The Contractor shall make his own interpretation of the data contained in said report, and the Contractor shall not be relieved of liability under the Contract documents for any loss sustained as a result of any variance between conditions indicated by or deduced from said report and the actual conditions encountered during the progress of the work.

DUST CONTROL: The work includes dust control as required for the alleviation or prevention of any dust nuisance on or about the site or the borrow area, or off-site if caused by the Contractor's operation either during the performance of the earthwork or resulting from the conditions in which the Contractor leaves the site. The Contractor shall assume all liability, including court costs of codefendants, for all claims related to dust or windblown materials attributable to his work.

SITE PREPARATION

Site preparation shall consist of site clearing and grubbing and the preparations of foundation materials for receiving fill.

CLEARING AND GRUBBING: The Contractor shall accept the site in this present condition and shall demolish and/or remove from the area of designated project earthwork all structures, both surface and subsurface, trees, brush, roots, debris, organic matter, and all other matter determined by the Soils Engineer to be deleterious or otherwise unsuitable. Such materials shall become the property of the Contractor and shall be removed from the site.

Tree root systems in proposed building areas should be removed to a minimum depth of 3 feet and to such an extent which would permit removal of all roots larger than 1 inch. Tree roots removed in parking areas may be limited to the upper 1½ feet of the ground surface. Backfill of tree root excavations should not be permitted until all exposed surfaces have been inspected and the Soils Engineer is present for the proper control of backfill placement and compaction. Burning in areas which are to receive fill materials shall not be permitted.

SUBGRADE PREPARATION: Surfaces to receive Engineered Fill, building or slab loads shall be prepared as outlined above, excavated/scarified to a depth of 12 inches, moisture-conditioned as necessary, and compacted to 90 percent relative compaction.

Loose soil areas, areas of uncertified fill, and/or areas of disturbed soils shall be moisture-conditioned as necessary and recompact to 90 percent relative compaction. All ruts, hummocks, or other uneven surface features shall be removed by surface grading prior to placement of any fill materials. All areas which are to receive fill materials shall be approved by the Soils Engineer prior to the placement of any of the fill material.

EXCAVATION: All excavation shall be accomplished to the tolerance normally defined by the Civil Engineer as shown on the project grading plans. All over-excavation below the grades specified shall be backfilled at the Contractor's expense and shall be compacted in accordance with the applicable technical requirements.

FILL AND BACKFILL MATERIAL: No material shall be moved or compacted without the presence of the Soils Engineer. Material from the required site excavation may be utilized for construction site fills provided prior approval is given by the Soils Engineer. All materials utilized for constructing site fills shall be free from vegetation or other deleterious matter as determined by the Soils Engineer.

PLACEMENT, SPREADING AND COMPACTION: The placement and spreading of approved fill materials and the processing and compaction of approved fill and native materials shall be the responsibility of the Contractor. However, compaction of fill materials by flooding, ponding, or jetting shall not be permitted unless specifically approved by local code, as well as the Soils Engineer.

Both cut and fill areas shall be surface-compacted to the satisfaction of the Soils Engineer prior to final acceptance.

SEASONAL LIMITS: No fill material shall be placed, spread, or rolled while it is frozen or thawing or during unfavorable wet weather conditions. When the work is interrupted by heavy rains, fill operations shall not be resumed until the Soils Engineer indicates that the moisture content and density of previously placed fill are as specified.

APPENDIX C

PAVEMENT SPECIFICATIONS

1. DEFINITIONS - The term "pavement" shall include asphaltic concrete surfacing, untreated aggregate base, and aggregate subbase. The term "subgrade" is that portion of the area on which surfacing, base, or subbase is to be placed.

The term "Standard Specifications": hereinafter referred to is the 2024 Standard Specifications of the State of California, Department of Transportation, and the "Materials Manual" is the Materials Manual of Testing and Control Procedures, State of California, Department of Public Works, Division of Highways. The term "relative compaction" refers to the field density expressed as a percentage of the maximum laboratory density as defined in the applicable tests outlined in the Materials Manual.

2. SCOPE OF WORK - This portion of the work shall include all labor, materials, tools, and equipment necessary for, and reasonably incidental to the completion of the pavement shown on the plans and as herein specified, except work specifically noted as "Work Not Included."

3. PREPARATION OF THE SUBGRADE - The Contractor shall prepare the surface of the various subgrades receiving subsequent pavement courses to the lines, grades, and dimensions given on the plans. The upper 12 inches of the soil subgrade beneath the pavement section shall be compacted to a minimum relative compaction of 90 percent. The finished subgrades shall be tested and approved by the Soils Engineer prior to the placement of additional pavement courses.

4. UNTREATED AGGREGATE BASE - The aggregate base material shall be spread and compacted on the prepared subgrade in conformity with the lines, grades, and dimensions shown on the plans. The aggregate base material shall conform to the requirements of Section 26 of the Standard Specifications for Class 2 material, 1½ inches maximum size. The aggregate base material shall be spread and compacted in accordance with Section 26 of the Standard Specifications. The aggregate base material shall be spread in layers not exceeding 6 inches and each layer of aggregate material course shall be tested and approved by the Soils Engineer prior to the placement of successive layers. The aggregate base material shall be compacted to a minimum relative compaction of 95 percent.

5. AGGREGATE SUBBASE - The aggregate subbase shall be spread and compacted on the prepared subgrade in conformity with the lines, grades, and dimensions shown on the plans. The aggregate subbase material shall conform to the requirements of Section 25 of the Standard Specifications for Class 2 material. The aggregate subbase material shall be compacted to a minimum relative compaction of 95 percent, and it shall be spread and compacted in accordance with Section 25 of the Standard Specifications. Each layer of aggregate subbase shall be tested and approved by the Soils Engineer prior to the placement of successive layers.

6. ASPHALTIC CONCRETE SURFACING - Asphaltic concrete surfacing shall consist of a mixture of mineral aggregate and paving grade asphalt, mixed at a central mixing plant and spread and compacted on a prepared base in conformity with the lines, grades and dimensions shown on the plans. The viscosity grade of the asphalt shall be PG 64-10. The mineral aggregate shall be Type B, ½ inch maximum size, medium grading and shall conform to the requirements set forth in Section 39. The drying, proportioning and mixing of the materials shall conform to Section 39.

The prime coat, spreading and compacting equipment and spreading and compacting mixture shall conform to the applicable chapters of Section 39, with the exception that no surface course shall be placed when the atmospheric temperature is below 50° F. The surfacing shall be rolled with a combination of steel wheel and pneumatic rollers, as described in Section 39-6. The surface course shall be placed with an approved self-propelled mechanical spreading and finishing machine.

7. FOG SEAL COAT - The fog seal (mixing type asphaltic emulsion) shall conform to and be applied in accordance with the requirements of Section 37.